

PLANTING LEGEND: Venturan Coastal Sage Scrub Planting Palette					
SYMBOL	NAME	MINIMUM REQUIREMENT	SIZE	QTY	DETAIL
○	<i>Artemisia californica</i>	Low	1.04' @ 3' O.C.	2787	A8.02A.19
○	<i>Callitris ligularis</i>	Low	1.04' @ 3' O.C.	2807	A8.02A.19
○	<i>Eriogonum fasciculatum</i>	Low	1.04' @ 3' O.C.	742	A8.02A.19
○	<i>Eriogonum fasciculatum ssp. fasciculatum</i>	Low	1.04' @ 3' O.C.	2098	A8.02A.19
○	<i>Callitris ligularis</i>	Low	1.04' @ 3' O.C.	152	A8.02A.19
○	<i>Malvastrum laevis</i>	Low	1.04' @ 3' O.C.	233	A8.02A.19
○	<i>Rhus integrifolia</i>	Low	1.04' @ 3' O.C.	139	A8.02A.19
○	<i>Sida molle</i>	Low	1.04' @ 3' O.C.	307	A8.02A.19
○	<i>Sida molle</i>	Low	1.04' @ 3' O.C.	78	A8.02A.19

REFER TO SHEET L1.10 FOR ALL PLANTING NOTES AND RESTORATION TASKS.

NOTE:
A. ALL EXISTING PLANTING AREAS NOT SHOWN FOR DEMO OR TO BE PLANTED SHALL REMAIN AS IS AND SHOULD BE PROTECTED IN PLACE. CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO PREVENT DAMAGE TO PLANTS OR SOIL COMPACTION, TYPICAL.
B. ALL EXISTING TREES TO REMAIN UNLESS STATED OTHERWISE CONTRACTOR TO PROTECT IN PLACE. ANY TREES TO BE DEMOLISHED SHALL BE VERIFIED AND APPROVED BY CLIENTS REPRESENTATIVE.

PLANTING LEGEND: Venturan Coastal Sage Scrub Hydrosed Mixture					
SYMBOL	NAME	MINIMUM REQUIREMENT	SIZE	QTY	DETAIL
○	<i>Artemisia californica</i>	9025	3"	-	-
○	<i>Callitris ligularis</i>	2142	0.5"	-	-
○	<i>Croton retusus</i>	NA	2"	-	-
○	<i>Callitris ligularis</i>	2080	3"	-	-
○	<i>Artemisia californica</i>	4050	2"	-	-
○	<i>Eriogonum fasciculatum</i>	3050	3"	-	-
○	<i>Eriogonum fasciculatum</i>	3070	2"	-	-
○	<i>Penstemon brevis</i>	5142	1"	-	-
○	<i>Halimolobos laevis</i>	9580	1"	-	-
○	<i>Isotria medeolae</i>	4050	1"	-	-
○	<i>Asplenium platyneuron</i>	9580	1"	-	-
○	<i>Lupinus succulentus</i>	9580	1"	-	-
○	<i>Artemisia californica</i>	NA	2"	-	-
○	<i>Callitris ligularis</i>	280	2"	-	-
○	<i>Mimulus aurantiacus</i>	9580	5"	-	-
○	<i>Stipa sp.</i>	9580	2"	-	-
○	<i>Sida molle</i>	2	-	-	-
○	<i>Sida molle</i>	7050	2"	-	-
○	<i>Syrinchium bellum</i>	2	-	-	-
○	<i>Blumea sp.</i>	1	-	-	-

PLANTING LEGEND: Cacti Thickets					
SYMBOL	NAME	MINIMUM REQUIREMENT	SIZE	QTY	DETAIL
○	Savago Cacti	Low	3' O.C.	-	A8.02A.19

- PLANTING NOTES**
- Contractor to refer to project mitigation report for all removal, salvage, and installation requirements and procedures.
 - Plant quantities are for REFERENCE ONLY. Contractor to provide and install all plant material shown on drawings.
 - Contractor to refer to mitigation report for proper soil preparation.
 - All container plants to be installed in holes that are the same size as the planting container.
 - The unshaded ground within each cactus thicket shall be covered with 3 inches of topsoil over mulch.
 - Seeding shall be conducted either by hand or as the final step in a two step hydrosed/mulch application.



OVERALL PLANTING PLAN
 1"=20'-0"

